

Room Cooling

Direct expansion air conditioners for IT Cooling

From 30 to 140 kW



x-MEXT


The perfect choice
for your data center



Direct expansion air conditioner for IT Environments From 30 to 140 kW

Range composition

3 compact modules which have 10 new sizes with inverter compressor and 14 sizes with on/off compressor.



Variable Drehzahl x-MEXT-i

Größe

Feste Drehzahl x-MEXT-f



Frame M
from 25
to 55 kW




Frame L
from 55
to 80 kW



Frame XL
from 80
to 140 kW

The best in every aspect




Full inverter technology

- 01.** Energy savings at partial loads
- 02.** Precise and reliable capacity regulation in any condition
- 03.** Lasting investment. The capacity increase accompanies the growth of your data center.



Unmatched performance

x-MEXT brings efficiency to another level. This performance coupling with excellent compactness creates a combination that makes it the most competitive solution on the market.



Full frontal accessibility

Service-oriented design means each component easily accessible for routine and extraordinary maintenance.

Applications

Complete package solution ideal for Enterprise Data centers


This product is the result of the highest quality and reliability standards from more than 50 years in the IT Cooling field. Complete solution for:


- 1. ENTERPRISE DC**
- 2. COLOCATION DC**
- 3. UPS ROOMS**
- 4. BATTERY ROOMS**

FAST DEPLOYMENT AND SCALABILITY

x-MEXT improves the scalability and rapid installation typical of direct expansion systems.

Complete solution made by the internal perimetral direct expansion unit and the external remote condenser or dry-cooler.





Technological Choices

Microchannel Coil

Innovative microchannel evaporator coil thanks to intensive research and development. In this way it has been possible to make the unit even more compact, achieving a very competitive footprint.

Variable Speed Compressor

High quality Scroll compressor that increases the level of efficiency. Thanks to the manufacturing and the high number of tests, reliability is guaranteed as never before.

With the new inverter driver the efficiency, reliability, and accuracy have increased.

It will be possible to control the compressor by improving its speed regulation while minimizing stress.



**Mitsubishi
Electric Quality**

x-MEXT grants the highest quality standards, thanks in part, to the adoption of specific Japanese design techniques.

Interfacing Devices



Compact keyboard (STD)



7 inch touch screen (opt.)



KIPLink (opt.)

EC Fan



Introduction of a new impeller, designed in-house that provides an unreachable hydraulic efficiency.

MEGR & MEDR Units



The new range of remote condensers & Dry-coolers allows you to choose the most suitable type of Fan from EC to AC.

In addition, for the remote condensers are available with different coils, either tube & fin or microchannel, and also different treatments.

Such as the Kako Tora, that studies and solves defects encountered by previous similar ranges, and Poka Yoke, that prevents possible new problems, and makes maintenance and service activities as easy as possible.

Available Versions

Total flexibility between internal and external units


Attention to operating costs and system reliability are always high in IT environments. For this reason, versions with Free-cooling and Dual Fluid systems find a perfect fit even in the most demanding plants.

SINGLE FLUID

DX To be paired with remote air-cooled condenser.




DW Equipped with built in water-cooled condenser.




DX and **DW** single-source versions are the simplest solutions to implement in a system.


FREE COOLING

DW-FC Equipped with build in water-cooled condenser + FC coil.

 FC INTEGRATION AVAILABLE




TEMPERATURE DISTRIBUTION AND OPERATING MODES




A bypass system allows dry-cooler water to be circulated internally to the water coil in order to work in **free-cooling** conditions.

DUAL FLUID SYSTEM

DX-DF FC AVAILABLE







DW-DF FC AVAILABLE



The ability to exploit **two independent sources**, to increase the redundancy of the system and facilitate routine maintenance.


Configurations

Several air deliveries available




Accessories

Rich choice of options




PLENUMS & DUMPERS

A wide selection of plenums and dumpers are available to fit any type of system. Specific mechanism ensures full accessibility to inner components.



UNINTERRUPTIBLE OPERATION

Thanks to a control BACKUP modul and ATS the units can ensure continuity of operations even in power failure circumstances.



EXTREME INSTALLATION

A devoted liquid receiver allows for the installation of very long lines (up to 100m) or in very low outdoor temperatures (down to -40 °C).

User Interface

State-of-the-art interface in terms of user experience

The 7" touch screen display (opt.) with easy-to-read color graphics ensures the immediate visualization of the units' status and provides simple alarms and event management.

Dedicated menus show the main operating parameters like temperature, humidity, and ventilation.

1 **INTUITIVE ICONS**
for a better user experience

2 **MULTILINGUAL**
13 available languages

3 **REAL-TIME DISPLAY**
of main operating variables

4 **QUICK MENU ACCESS**



KIPLink Connectivity

Based on proprietary technology, KIPLink allows one to operate the unit directly from a mobile device smartphone, tablet, or notebook.

REMOTE CONTROL

In local network (LAN) of building or remotely through VPN with internet browser.

- BROWSER



LAN PORT

With a simple Ethernet connection, it is possible to connect KIPLink to the facility LAN and get full access to the unit's control with a browser.

WI-FI KEYBOARD

Close to the unit with MEHITS APP access.

- MOBILE DEVICE



LOCAL WI-FI



Direct access is achieved by scanning the QR-code positioned on the front side of the unit.



Factory Acceptance Test Experience

Test your unit before installation and make sure its performance is totally reliable.



Factory Acceptance Test

Factory Acceptance Test is available as additional service in order to test the unit under specific conditions.



Carried out within modern and sophisticated facilities, this service gives the customer the possibility to choose among different test options in order to:

- Verify unit operation under severe conditions
- Check performance, both at full and partial loads
- Test the unit with low outdoor air temperature operation
- Detect sound emissions
- Time the fast restart

**TO LEARN MORE ABOUT
FACTORY ACCEPTANCE TEST**

<https://www.youtube.com/watch?v=Cy2FXAfhvj8>



**MITSUBISHI ELECTRIC
HYDRONICS & IT COOLING SYSTEMS S.p.A.**

Head Office:

Via Caduti di Cefalonia 1 - 36061 Bassano del Grappa (VI) - Italy

Tel (+39) 0424 509 500 - Fax (+39) 0424 509 509

www.melcohit.com